

LIME STONE FOR  $\text{CaCl}_2$  PLANT  
 $\text{CaCO}_3$ : >95% W/W; 93% W/W(MIN.)  
 $\text{CaO}$ : 51 TO 54% W/W  
 $\text{MgO}$ : MAX. 1.0% W/W ON EACH  
SUPPLY BUT COMPOSITE AVERAGE  
ON MONTHLY BASIS SHOULD NOT BE  
MORE THAN AVERAGE 0.85% W/W  
ACID INSOLUBLE : MAX. 1.5% W/W  
LOI: 41 TO 44% W/W  
COLOUR: GREY  
IRON + ALUMINA : MAX. 0.8% W/W  
SIZE: 1.0" TO 2.0"  
BULK DENSITY : 900 KG/M<sup>3</sup>  
MATERIAL SHOULD BE SUPPLIED  
ONLY AFTER THOROUGHLY WASHING  
TO MAKE IT DUST FREE

Approx. Annual Requirement : 6000 MT  
Approx. Monthly Consumption: 500 MT